



Project Name:

Contact:

**Building Solutions**

Ceramic tile adhesives  
and grouts, waterproofing  
and repair products

info@constructionchemicals.com.au  
www.constructionchemicals.com.au

**Adelaide**  
49-57 Davis St  
Wingfield SA 5013  
Phone (08) 8243 7888  
Fax (08) 8243 7800

**Brisbane**  
45 Coulson St  
Wacol QLD 4076  
Phone (07) 3271 2944  
Fax (07) 3271 3892

**Darwin**  
4/4 Aristos Pl  
(off Farrell Cres)  
Winnellie NT 0820  
Phone (08) 8947 1811  
Fax (08) 8947 1819

**Melbourne**  
11 Gabrielle Ct  
Bayswater North VIC 3153  
Phone (03) 9761 4711  
Fax (03) 9761 4748

**Perth**  
11 Collie St  
Welshpool WA 6106  
Phone (08) 9356 9999  
Fax (08) 9356 9955

**Sydney**  
31-33 Newton Rd  
Wetherill Park NSW 2164  
Phone (02) 9756 3533  
Fax (02) 9756 3534

**Auckland**  
16 Carpenter Rd  
East Tamaki  
Phone (09) 273 5444  
Fax (09) 273 5442

**Kuala Lumpur**  
Lot 2 Jalan Kecapi  
33/2 Elite Industrial Estate  
Off Jalan Bukit Kemuning  
40000 Shah Alam  
Phone (603) 5122 2522  
Fax (603) 5122 2526

**Construction Chemicals  
WATERPROOFING SPECIFICATION**

**2.1 WATERPROOF MEMBRANES  
STANDARDS.**

Waterproofing material shall comply with the following standards.  
**AS 3740 and local regulations.**

**2.1.1 GUARANTEE**

The waterproof membrane manufacturer to provide a written guarantee for the whole of the waterproofing work, against failure due to defective material for a period of ten (10) years after the date of final completion.

**2.1.2 SURFACE PREPARATION**

The surface to be waterproofed must be free of grease, oil, dust and other contaminants.

The surface to be waterproofed must be primed Internally with **Primebond** Made by **Construction Chemicals Pty Ltd.**

Prime externally with **Primax** Made by **Construction Chemicals Pty Ltd.**

**2.1.3 All waterproofing to be carried out shall be installed by an applicator approved by the manufacturer to obtain a ten (10) year product guarantee,**

**2.14 Any deviation from the materials specified in this schedule must be approved by the Architect in writing only.**

**2.1.5 SCHEDULE**

INTERNALLY :

Provide and install in all areas to be waterproofed ..... waterproof membrane manufactured by Construction Chemicals, strictly in accordance with the manufacturers written instructions.

All areas in which the waterproof membrane is installed shall be **water Tested 24 hours** prior to the laying of the bed over the finished membrane. The membrane must be allowed to cure for 24 hours prior to water testing.

**2.1.6 EXTERNALLY.**

Provide and install in all external locations..... waterproof membrane, manufactured by Construction Chemicals, strictly in accordance with the manufacturers written instructions.

**2.1.7 Waterproof membrane must be allowed to cure for a minimum of 24 hours prior to fixing tiles or a screed bed over the finished membrane.**