



Factory sealed CLD[®] Structural Cavity batten located at panel joints.

Deck waterproof membrane carry up behind building underlay past wall framing bottom plate.

*Drain holes in James Hardie uPVC vent strip to achieve the required ventilation openings of 1000mm² per lineal metre